


New Public Works Building Proposal


Lehigh Township
Building Committee
2018

- The new building is proposed to be a 22,660 sf pre-engineered metal building with a drive through design and attached low roof office/break/bathroom wing.
- Based on the programming and schematic plan, we have developed the attached Order of magnitude cost budget for the building, at a cost ranging from \$3,500,000 to \$3,950,000.
- These costs are based on the 2018R.S. Means cost estimating data and our historical project data.
- This budget excludes site costs and misc. items as requested and noted on the attached document.





Maintenance Building



Maintenance Garage Plan



Maintenance Garage Interior

General:

- Want Durable, functional, practical building
- 100' x 200' garage
- Pre-engineered metal building with continuous foundation
- Piers 8" to 12" above finished floor. Column not on floor.
- 8' high perimeter masonry wall, could be painted block or colored split face. - most cost effective. Insulate inside the block cores
- Prefer Earth tone colors

Office Wing:

- Exterior split face block, lower roof line.
- Epoxy floor with colored chips through-out.
- Select materials to be able to hose down the space.
- All interior walls to be painted block.
- Use temp mats at doors
- ACT ceiling
- Propane, ducted heat and air-conditioning.
- Furnace room: one boiler for shop, one split for office.
- Windows as appropriate. All fixed, non-operable.

Garage:

- Parts & Tire Rooms - 8' Block wall with deck
- In-floor Radiant heat.
- Lifts: Surface mount by owner - no heat under. Do not include lift in the budget. (2) lifts total, (1) 15,000 #
- Provide CO sensor / fans. Also include fan to ventilate buildings.
- Include Waste oil heater, 275 gal floor cabinet type with day tank and storage. Provide close to OH doors.
- Exclude oil/fluid piping / reels.
- New air compressor & piping - included in budget.
- Approx. 8 windows in garage up high, plus windows as appropriate in office wing.
- Concrete slab: Would like Bridge mix (higher quality slab), oil/salt sealer, etc.

Roof

- Structure designed to support future solar on south side.
- Snow guards on all roofs.
- Ridge design to prevent blowing snow/rain from entering.

Doors

- 20' w x 16' h overhead door at ends
- 20' wide x 12' or 14' high at side (for backup existing).
- Small typical windows in OH doors.
- Man door at each OH door.
- Main entrance into office area to have glass entry.
- Man door - small glass for security?
- Keys: Just master level keys, No electronics or FOB's
- Remotes on O.H. door

Electrical

- LED lighting
- Include Big Ass Fans.
- Electric setup for future solar and Sub Panel for office.
- Separate switching of lights.
- Extra lights with higher footcandles in shop near office entry.
- Security lighting on exterior. South side shielded.
- Generator for critical power items in public works and police (optional - alternate cost)

Include CAT 5 to 10 locations

- Data/computers freestanding - not tied to office.
- Include CAT 5 to 10 locations
- Include WIFI locations
- Phone - Ironton is phone service provider.
- Provide 2 conduits between this garage building & Township office

Security/Cameras: Not included in budget.

Fire Alarm / Sprinkler - Just provide what is code required

Plumbing:

- Provide 1 ½” or 1 ¼” hose bib
- Need pressure tank
- Trench drain: 12” wide, Stainless steel angles, cast iron grates
- Oil separator
- Sanitary (pubic sewer on North or East, North is a force main)

Civil cost excluded in this budget. Assume site is pad ready. Geotech as part of civil engineering scope.

Exclude fuel station. They will continue to use existing.



WATKINS ARCHITECT LTD
 PRESIDENT: JOHN C WATKINS
 POST OFFICE BOX 412
 FLEETWOOD, PA 19522
 PHONE: (610) 944-5536
 FAX: (610) 944-5539
 WWW.WATKINSARCHITECT.COM
 WWW.SYNERGETICS-ARCHITECTS.COM

Lehigh Township public works building - Order of magnitude schematic budget 6/15/2018

Description	qty / square footage	Low range		high range
New public works office	2100	\$261,220.00	to	\$276,960.00
New public works garage with Metal panels	20515	\$2,586,184.00	to	\$2,909,880.00
		Subtotal		\$3,186,840.00
Architectural / Engineering	7%	\$199,318.28		\$223,078.80
Soft Costs / Contingency	15%	\$427,110.60		\$478,026.00
		Total		\$3,887,945